

Sharif University of Technology Scientia Iranica Transactions A: Civil Engineering http://scientiairanica.sharif.edu



Systematic approach to the design of modular military housing units using six-sigma

B.-H. Cho^a, D.-J. Kim^{b,*}, and T. Ha^c

a. Department of Architectural Engineering, Ajou University, 206 Worldcup-ro, Yeongtong-gu, Suwon-si, Gyeonggi-do 16499, South Korea.

b. Department of Architectural Engineering, Kyung Hee University, 1732, Deogyeong-daero, Giheung-gu, Yongin-si, Gyeonggi-do 17104. South Korea.

c. Steel Solution Center, POSCO, 100 Songdogwahak-ro, Yeonsu-gu, Incheon 21985, South Korea.

Received 16 October 2016; accepted 27 January 2018

KEYWORDS

Six-Sigma; Modular construction; Quality function deployment; Military housing unit; Steel structure. Abstract. Military quarters and barracks are representative of housing units where the same plan is repeated and, thus, prefabricated housing production can be effectively applied. These housing units are required to be disassembled and recycled as military forces are frequently reorganized and deployed to perform military actions. In order to meet these needs, this study proposes a systematic approach to the design of modular military housing units based on Six-Sigma concept. The application of Six-Sigma to modular military housing units allows customers' needs to be reflected on the critical-to-quality parameter, which summarizes the main design requirements. In addition, the design concept of the modular units can be developed based on the derived critical-to-quality functionalities. To evaluate the effectiveness of the proposed approach, a representative example of military housing units is chosen and designed by utilizing the new modular units developed through this procedure. The weight of frames per unit area and factory manufacturing ratio of the new design are analyzed. The results of the comparison show that the use of the new modular units not only reduces construction cost significantly, but also greatly improves the quality of construction.

© 2019 Sharif University of Technology. All rights reserved.

1. Introduction

Modular construction can be defined as a threedimensional volumetric unit that can be manufactured in a factory, delivered to the construction site, and assembled as the main structural elements of the building [1]. It has been widely applied to many different types of building construction in Europe and

 Corresponding author. Tel.: 82 31 201 3329 Fax: 82 31 202 8854 E-mail addresses: bhcho@ajou.ac.kr (B.-H. Cho); djkim@khu.ac.kr (D.-J. Kim); hath@posco.com (T. Ha) Japan. In Korea, it has been applied mainly to school buildings and military facilities [2].

Military barracks and Bachelor Officers' Quarters (BOQs) are representative housing units that use the same plan repeatedly, which makes them good candidates for prefabricated housing production. These housing units must be disassembled and recycled because military forces are frequently reorganized and deployed to various locations. In Korea, the military owns 100,000 buildings nationwide in a total area of 25.2 million m²; however, approximately 30% of the building facilities are more than 20 years old. Therefore, new construction methods are required to improve the quality of military facilities. For this purpose, modular construction has been applied in Korea to



Figure 1. Modular military facilities in Korea.

the construction of platoon barracks, military offices, battalion barracks, and BOQs, as shown in Figure 1. In the process of applying modular construction to military facilities, the important factors include cost reduction through the standardization of construction units and reusability of the construction elements that are disassembled at the end of their useful life. Most existing military modular construction facilities in Korea fail to meet those requirements [3].

In order to address this issue, this study develops new military housing units based on the so-called Six-Sigma methodology [4]. The Six-Sigma was first developed by Motorola in the 1980s [5] and became well-known in the 1990s when Jack Welch applied it to develop strategies for his company, General Electric. The application of the Six-Sigma to modular military housing units allows customers' needs to be reflected on the critical to quality, which summarizes the main design requirements. The design concept of the modular units can be developed based on the Critical To Qualities (CTQs). To evaluate the effectiveness of the proposed approach, a representative example of military quarters is chosen and designed by utilizing both the new modular units developed through this procedure and existing modular units. The frame mass per unit area and prefabrication ratio of the two cases are compared and analyzed.

2. Derivation of CTQ for modular military housing

In order to derive the requirements for modular military housing units, potential customers are grouped into one of the two following categories: external and internal customers. The former consists of design firms, module manufacturers, and contractors; the latter includes owners and residents. The requirements of the two customer groups for the modular military housing are listed in Table 1, which summarizes the results of customer interviews. In the table, "raw data", which are also called the voice of customers, represent the customers' opinions on existing military modular units, and "required quality" represents the quality of the product required to reflect the customers'



Figure 2. House of quality for quality function deployment analysis.

opinions. The required quality derived from the Voice Of Customer (VOC) in the interviews can be converted to quality characteristics for design through the House Of Quality (HOQ) structure, as illustrated in Figure 2. The HOQ organizes items based on the required qualities given in Table 1. The importance and satisfaction of each item are assessed through a survey of customers.

Figure 3 shows the importance and satisfaction evaluation of the customers' requirements. The items of "short construction period", "easy to disassemble", "compatible to other modules", and "low construction cost" are considered to be highly important; however, the evaluation of the performance of the existing system regarding these items receives low ratings. Based on these results, Table 2 provides the priority rating on the customers' required qualities. Based on the results of the table, items with high priority are found to include "easy to disassemble", "reduction of construction cost", and "shortening of construction time period."

This study uses the Quality Function Deployment

Voice of Customers (raw data)		Scene	Required quality		
		Who, where, when			
Architect	Poor exterior design	Architects design modular buildings using the developed modules	Introduction of various exterior designs		
Module	Using too many kinds of materials	Manufacturers reserve key materials for modules in stock at the factory	Using standard materials		
manufacturer	Difficult to deliver modules. High cost for delivery	Manufacturers deliver modules to the construction site	Easy delivery of modules		
Contractor	Damage occurring during delivery and installation of modules	Contractors install modules at construction site	Safe for rainfall and minimized damages during delivery		
Owner	Higher construction cost than that of conventional methods	The owner compares the costs of traditional and modular construction methods	Low construction cost		
e wher	Not easy to reuse	The owner disassembles modules to deploy military forces after using them many years	Easy to disassemble and deliver		
User	Poor residential performance of existing modular buildings	Residents stay in the housing after work	Excellent thermal, optical, and sound performances		

Table 1. Requirements of potential customer groups.



Figure 3. Importance and satisfaction evaluation of the customer's requirements.

(QFD) methodology to convert customers' required qualities into the quality characteristics of the products to be developed. The QFD methodology is a tool that can make a quantitative evaluation of the relation between the customer required qualities and product characteristics using a correlation matrix [6]. The results of the analysis using the correlation matrix are provided in Table 3. Based on the correlation analysis, parameters that are critical to quality from the customers' perspective can be

Customers' required quality	(1) Importance rating	(2) Satisfaction rating	(3) Possible quality levels	(4) Level-up ratio	(5) Sales Point	(6) Absolute priority	Priority ratio (%)	Rating
Easy to supply material	3.9	3.4	5	1.5	—	5.8	5.4	6
Less extra cost	3.7	2.7	3	1.1	_	4.0	3.7	11
Easy delivery	4.5	3.2	5	1.6	۲	10.7	9.9	4
Short construction period	4.7	1.9	5	2.7	-	12.7	11.8	3
Easy to disassemble	4.7	1.4	5	3.5	۲	24.7	23.0	1
Compatible to other modules	4.5	1.6	3	1.9	0	10.2	9.5	5
Less construction cost	4.3	2.5	5	2.0	۲	12.9	12.0	2
Less energy consumption	3.9	2.9	2	1.0	_	3.9	3.6	13
Less hot in summer	4.5	2.6	2	1.0	-	4.5	4.2	9
Less cold in winter	4.5	2.5	3	1.2	_	5.4	5.0	7
Good daylight performance	4.0	3.0	2	1.0	_	4.0	3.7	11
Good sound insulation	4.6	2.8	2	1.0	-	4.6	4.3	8
Good ventilation	4.2	2.9	2	1.0	-	4.2	3.9	10

Table 2. Priority rating of the customers' required qualities.

(1) Importance rating: Values obtained from customer survey $(1 \sim 5)$;

(2) Satisfaction rating: Values obtained from customer survey $(1 \sim 5)$;

(3) Possible quality levels from a viewpoint of developers $(1 \sim 5)$;

(4) Level-up ratio: (3)/(2);

(5) Sales point from a viewpoint of developers (\odot : 1.5, \circ : 1.2, no symbol: 1.0);

(6) Absolute priority: $(1) \times (4) \times (5)$.

derived. Among 11 quality characteristics in the table, the top 6 are selected as the parameters Critical To Quality (CTQs) and used to set up development targets.

Next, the development targets can be set by analyzing the current levels of the potential CTQs in Table 3 and performing a benchmarking analysis. The benchmark target of this study is set by referring to a military modular system developed by a UKbased company, Corus Living Solutions (CLS) [7]. The target levels of the potential CTQs are summarized in Table 4. Among them, "no. of module types", "no. of types of structural members", and "no. of connections during on-site construction" are difficult to quantify consistently, and "module length" does not contribute significantly to module improvement. Therefore, "factory manufacturing ratio" and "weight of frames per unit area" are chosen as the final CTQs.

3. Derivation of design concepts

Based on the selected CTQs in the previous section, key functions are derived to design a new modular military housing unit. A correlation analysis between the quality characteristics and key functions is performed, as shown in Table 5. The results of the analysis indicate that highly prioritized functions include "connecting exterior panels", "connecting plumbing pipes", "waterproofing during delivery", "connecting corridor panels", and "loading on trailer".

Table 6 shows possible solutions for each key function. For instance, three solutions are available for the required functions of "connecting exterior panels" and "connecting corridor panels." Possible design concepts can be developed by combining the available solutions for each key function. An example of a design concept obtained by a combination of solutions

					Quality cl	iara	cteri	stic						
	Weight Reusability			Standa	Standardization			on of	of Residential					
	Weight Reusability 5			Standa	i dization	modules			performance					
Customers' required quality	Weight of frames per unit area	Factory manufacturing ratio	Number of connections during construction at site	Number of types of structural members	Number of module types	Module height	Module length	Module width	Window area ratio	Sound insulation	Thermal insulation	Absolute priority	Priority ratio (%)	Rating
Easy to supply material	_	_	_	۲	0	-	-	-	-	_	_	5.8	5.4	6
Low extra cost	0	0	-	0	۲	-	-	-	-	-	-	4.0	3.7	11
Easy delivery	0	-	-	-	—	0	۲	0	-	-	-	10.7	9.9	4
Short construction period	-	۲	٢	-	\bigtriangleup	-	—	-	-	_	-	12.7	11.8	3
Easy to disassemble	-	۲	۲	-	\bigtriangleup	-	-	-	-	-	-	24.7	23.0	1
Compatible to other modules	-	-	-	-	۲	-	-	-	-	-	-	10.2	9.5	5
Low construction cost	۲	-	—	۲	—	0	0	0	-	-	-	-12.9	12.0	2
Low energy consumption	—	—	-	_	—	-	-	-	0	-	۲	3.9	3.6	13
Less hot in summer	-	—	-	-	—	-	-	-	0	-	۲	4.5	4.2	9
Less cold in winter	-	-	-	-	—	-	-	-	0	-	۲	5.4	5.0	7
Good daylight performance	-	-	—	-	—	0	-	-	۲	-	-	4.0	3.7	11
Good sound insulation	-	-	—	-	—	-	-	-	-	۲	-	4.6	4.3	8
Good ventilation	-	—	—	-	—	0	-	-	۲	-	-	4.2	3.9	10
Absolute priority	160	349	337	180	183	95	135	71	115	41	124	-	100	-
Priority ratios $(\%)$	8.9	19.5	18.8	10.1	10.2	5.3	7.5	4.0	6.4	2.3	6.9	_	-	-
Ratings	5	1	2	4	3	9	6	10	8	11	7	_	_	

 Table 3. Correlation analysis between customers' required qualities and quality characteristics.

Table 4. Target levels of the potential CTQs.

Potential CTQs		Factory manufacturing ratio	No. of connections during construction on site	No. of module types	No. of types of structural members	Weight of frames per unit area	Module length
CTQ priority ratio (%)		19.5	18.8	10.2	10.1	8.95	7.54
Default level		42%	$0.15~{\rm per}~{\rm m}^2$	5	6	$0.76~\mathrm{kN/m^2}$	$6 \mathrm{m}$
Target level		70%	$0.1 \mathrm{ per} \mathrm{m}^2$	4	3	$0.59 \ \mathrm{kN/m^2}$	6 m
	\mathbf{Level}						
Competitive	5	-		+			
benchmark	4						
★ Benchmark class	3	•					

 $\mathbf{2}$

1

• Default level

 $\blacksquare Target \ level$

		Key functions															
	Deli	livery Assembly of modules				Performance of modules											
Quality characteristics	Waterproofing during delivery	Loading on trailer	Passing under viaduct	Lifting modules	Locating modules	Connecting corridor panels	Connecting plumbing pipes	Connecting electric pipes	Connecting interior panels	Connecting exterior panels	Resisting vertical loads	Resisting horizontal loads	Waterproofing	Sound insulation	Thermal insulation	Fireproofing	Drainage
Factory manufacturing ratio	۲	о	-	-	-	0	۲	0	0	٢	-	-	0	-	-	-	-
Number of connections at site	0	-	-	-	—	٢	٢	0	-	۲	-	0	—	—	-	0	-
Number of kinds of modules	-	-	-	-	0	-	-	-	-	-	0	-	—	-	-	-	-
Number of kinds of structural members	_	-	_	۲	_	_	_	_	-	_	_	_	_	_	_	_	_
Weight of frames per unit area	-	۲	-	۲	0	-	-	-	-	_	0	0	-	-	-	-	-
Module length	_	-	_	_	—	_	_	_	_	_	-	_	—	0	0	_	-
Thermal insulation	_	-	-	-	_	_	_	-	-	_	-	_	_	_	-	_	-
Window area ratio	-	-	-	-	-	-	-	-	-	ο	-	-	-	-	٢	-	-
Module height	-	-	٢	-	-	-	-	-	-	-	-	-	-	-	-	-	0
Module width	-	۲	-	-	-	-	-	-	-	_	-	-	-	-	-	-	-
Sound insulation	-	-	-	-	—	—	-	-	_	-	_	—	—	٢	-	-	-
Priority ratio (%)	10.6	8.0	2.2	7.8	2.6	10.4	15.7	5.2	2.7	16.6	2.6	3.8	2.7	2.0	3.7	2.6	0.7
Rating	3	5	15	6	12	4	2	7	10	1	12	8	10	16	9	14	17

Table 5. Correlation between the quality characteristics and key functions.



Figure 4. An example of a design concept obtained by a combination of solutions.

is shown in Figure 4. A total of five design concepts are derived by following this procedure. A Pugh matrix is created to select the optimal design among the candidates listed in Table 7. In this table, a relative evaluation of each candidate is carried out by comparing it with the design of the existing modular system for each of the key criteria. The results of the table indicate that the design concept (2) is the optimal one. Thus, it is selected as the final design of the new military modular housing unit.

4. Detailed design and design verification

4.1. Detailed design

In this section, a detailed design is created based on the concept derived from the previous section. Figure 5 shows the plan of a representative example of Reinforced Concrete (RC) military housing units in Korea. The developed modular design concept is applied to the design of this representative example.

The military housing unit for a single person is



Table 6. Possible solutions for each key function.

designed to have the same size similar to the factorybuilt module with a width of 3.3 m. Windows and pipe shafts are included in the unit to maximize the factory manufacturing ratio. Table 8 presents the results of a detailed unit room design. The cross-sectional details of the representative example are given in Table 9. The sloped roof frame is integrated into top story units to minimize the weight of frames per unit area while increasing the factory manufacturing ratio. The detailed frame design of the representative example is

Design concept		Default	Concept 1	Concept 2	Concept 3	Concept 4	Concept 5	
Key criterion	W eight							
Frame cost	5	S	S	+	S	S	+	
Easy delivery	3	\mathbf{S}	+	+	+	—	-	
Reusability	5	\mathbf{S}	\mathbf{S}	+	—	+	+	
Site construction	2	S	_	1	_	<u></u>	<u>т</u>	
time	5	C.		Т		Т	I	
Military	4	S	S	S	_	+	_	
design guide	т	d	0	6	Ι	Ι		
$\operatorname{Manufact}\operatorname{uring}$	4	\mathbf{S}	+	_	\mathbf{S}	_	_	
Compatibility	4	\mathbf{S}	+	_	\mathbf{S}	+	S	
Creativity	2	\mathbf{S}	S	+	+	S	\mathbf{S}	
Sum of positives		0	3	5	3	4	3	
Sum of negatives		0	1	2	2	2	3	
Sum of the sames		8	4	1	3	2	2	
Weighted sum of p	ositives	0	12	18	10	16	12	
Weighted sum of ne	egatives	0	-3	-8	-7	-8	-12	

Table 7. Derivation of the final design concept using a Pugh matrix.



Figure 5. Plan of a representative example of RC military housing units.

illustrated in Table 10. As shown in the table, four types of unit frames are assembled to form a single frame unit, and the double-sided corridor is attached on the side of the module in the form of a cantilever. In addition, duplicated column sections are eliminated to optimize the design of frame modules. Figure 6 shows the plan and bird's-eye view of the final design of the representative military housing units, which has 20 modular unit rooms and is constructed by combining totally 29 modular units.

		1 1 0						
Key function	(Connecting exterior panels						
considered	(Connecting plumbing pipes						
Design factor	Design of a unit module plan							
Definition	Design o	f a unit module for a single person						
	As is	To be						
- Unit plan base 3.6 m × length - Pipe shafts loc side between two	d on RC frames: width of of 4.5 m = 16.2 m^2 ated on the wall o units	 Determining width and length considering easy delivery: width of 3.3 m× length of 4.9 m = 16.17 m² Pipe shafts located on the corridor side of the bathroom Module width 3.3 m 						
Module In the second se	e width 3.6 m Pipe shafts n of RC BOQ	Wide window frame Pipe shafts Plan of modular BOQ						
Design point	- Determine the width and - Design pipe shafts to max	length suitable for easy delivery cimize the factory manufacturing ratio						
Expected effects	Satisfy the military design	criteria						
Results	Plan the drawing of a unit	Plan the drawing of a unit room						

Table 6. Detailed unit foom design of the representative example.	Table 8	. Detailed	unit room	design	of the	representative example	э.
--	---------	------------	-----------	--------	--------	------------------------	----

4.2. Design verification

In this section, a design verification of the final product of the military housing units developed in the previous section is performed. The adequacy of the developed system is investigated by evaluating the achievement of the target levels of the two final CTQs listed in Table 4. The results of the verification are summarized in Table 11.

The achievement level of the first CTQ, which is the factory manufacturing ratio, is assessed based on the ratio of manufacturing cost to the total construction cost excluding foundation and transportation. The results of the table indicate that the factory manufacturing ratio of the final product is 75.2%. Considering that the corresponding value of the existing modular military housing units is 42.9%, it is almost 80% improvement and exceeds the target value, which is 70%. This is possible mainly because most of the piping lines and internal finishing are manufactured in the factory, thus resulting in better product quality. The weight of frames per unit area of the developed modular system, which is the second CTQ, is 0.60 kN/m^2 , which is also greater than the target value, 0.59 kN/m^2 . This is only 62% of the corresponding value of the existing modular system. Consequently, the results of the comparison show that the use of the new modular

Key function		- Connecting exterior par	nels.					
considered	- Connecting plumbing pipes.							
Design factor	Design of a cross-section.							
Definition	Design of a cross-section of the representative example.							
	As is To be							
	- Sloped roof with 1/10 slope.							
- RC frame unit plan.	- Ensure at least the ceiling height of 2.4 m.							
- Ceiling height: 2.4 m	Average ceiling height of top story is higher than 2.4 m.							
- Roof slope: $3/10$.	- Horizontal pipes are located at the ceiling of corridor.							
	- Vertical pipes are connected at the underground pit.							
		·						
Section	n of RC BOQ	Se	ction of RC BOQ					
Design point	Minimizing module height wi	nile satisfying the military	design criteria.					
Expected effects	Enhanced cost-effectiveness d	ue to reduced story heigh	nt.					
Results	Planning the drawing of a un	it room.						

Table 9. Detailed cross-sectional design of the representative example.



Key functions	Connecting corridor panels
considered	Loading on trailer
Design factor	Design of frames
Definition	Design of frames of the representative example
	To be

⁻ Using four different modules

- Using roof-structure integrated modules
- Using cantilevered corridor modules
- Delivering two modules at a time







Figure 6. Plan and bird's-eye view of the newly designed military housing units.

	0	-		
\mathbf{CTQs}	Verification method	Target value	Design result	
Fastawy	Ratio of manufacturing cost to			
	the total construction cost	70%	75.9%	
manuracturning	excluding foundation and	1070	10.270	
ratio	transportation			
Weight of frames	Weight of steel frames	$0.50 \text{ kN}/m^2$	0.60 kN/m^2	
per unit area	divided by floor area	0.53 KN/III	0.00 km/m	

Table 11. Verification of the designed final product.

units not only reduces construction cost significantly, but also greatly improves the quality of construction.

5. Concluding remarks

This study proposed a systematic approach to the design of modular military housing units based on Six-Sigma concept. The application of the Six-Sigma to modular military housing units allows customers' needs to be reflected on the CTQ, which summarizes the main design requirements, and the design concept of the modular units can be developed based on the derived CTQs. To evaluate the effectiveness of the proposed approach, a representative example of military housing units was chosen and designed by utilizing the new modular units developed through this procedure. The weight of frames per unit area and the factory manufacturing ratio of the new design were analyzed. If compared to the existing modular system, the former is improved by 80%, and the latter is reduced by 62%. This indicates that the use of the new modular units not only reduces construction cost significantly, but also greatly improves the quality of construction.

Acknowledgement

This work was supported by a National Research Foundation of Korea (NRF) grant funded by the Korean government (Ministry of Science, ICT & Future Planning) (No. 2017R1A2B4004729).

References

- Lawson, R.M. and Ogden, R.G. "Hybrid' light steel panel and modular systems", *Thin-Walled Structures*, 46(7-9), pp. 720-730 (2008).
- Hong, S.-G., Cho, B.-H., Chung, K.S., and Moon, J.H. "Behavior of framed modular building system with double skin steel panels", *Journal of Construction Steel Research*, 67(6), pp. 936-946 (2011).
- Park, J.S. and Park, T.K. "A study on modular construction method in military facilities", *Proceedings* of AIK Spring Conference, **01**, pp. 565-570 (2006).
- 4. Ha, T.-H., Cho, B.-H., Kim, H., and Kim, D.-J. "Development of an efficient steel beam section for

modular construction based on six-sigma", Advances in Materials Science and Engineering, Article ID 9687078, 13 pages (2016).

- Pheng, L.S. and Hui, M.S. "Implementing and applying six-sigma in construction", *Journal of Construction Engineering and Management*, ASCE, **130**(4), pp. 482-489 (2004).
- Hassan, A., Siadat, A., Dantan, J.-Y., and Martin, P. "Conceptual process lanning-an improvement approach using QFD, FMEA and ABC methods", *Robotics and Computer-Integrated Manufacturing*, 26(4), pp. 392-401 (2010).
- Lawson, M., Ogden, R., and Goodier, C., Design in Modular Construction, CRC Press (2014).

Biographies

Bong-Ho Cho is a Professor at the Department of Architectural Engineering at Ajou Hee University, Suwon, Korea. He received his BS, MS, and PhD from the Department of Architecture, Seoul National University, Seoul, South Korea in 1996, 1998, and 2002, respectively. His current research interests include modular (prefab) construction and seismic structural engineering.

Dae-Jin Kim is an Associate Professor at the Department of Architectural Engineering at Kyung Hee University, Yongin, Korea. He received his BS and MS from Seoul National University in Korea in 1998 and 2000, respectively, and his PhD from the University of Illinois at Urbana-Champaign in 2009. His research interests include the composite structure design and analysis, partition of unity-based finite element analysis technique, and strut-and-tie modeling of reinforced concrete members.

Taehyu Ha is a Principal Researcher at the Steel Solution Center, Posco, Incheon, South Korea. He received his BS, MS, and PhD from the Department of Architecture, Seoul National University, Seoul, South Korea in 2000, 2002, and 2008, respectively. His research interests include constructional steel materials and seismic design of tall building structures.